

April 28, 2023

**ADDENDUM NO. 1  
SABINE RIVER AUTHORITY OF TEXAS  
Lake Fork Paving Projects RFB# 23-0702**


**THIS ADDENDUM IS ISSUED FOR THE PURPOSE OF AMENDING THE CONTRACT DOCUMENTS FOR THE SABINE RIVER AUTHORITY OF TEXAS, AS FOLLOWS:**

Bid Form

- Delete Page 21 replace with the attached. Bid Item 15 added for pulvamix of existing roadway at the S & R Cabin.

Clarifications

- Asphaltic spoil from the LFD Office Area can be stock piled for SRA at the existing maintenance shop, located near the intersection of SH 182 and FM 288 near the Dam Spillway, approximately 1 mile south of the Office location.
- SRA will assist with traffic control at the Office Site, and Hwy 14 Ramp location. SRA will post notifications and early signage to notify the public of closures. SRA will coordinate employee parking and access to the LFD Office location as required for contractors work.
- The load rating for the spillway service road bridge is 61,000 lb.



April 28, 2023

END

|     |       |    |   |    |      |
|-----|-------|----|---|----|------|
| 13. | 200   | LF | <b>Apply reflectorized pavement markings</b> , provide all labor, materials, equipment, tools, to apply reflectorized pavement markings on asphalt concrete pavement surfaces per TXDOT Item 666, all in accordance with the plans, specifications, and scope of work.<br><b>Location: Office Parking</b>   |    |      |
|     |       |    | DOLLARS   |    |      |
|     |       |    | CENTS   | \$ | \$ * |
|     |       |    | Per Linear Foot   |    |      |
|     |       |    |   |    |      |
| 14. | 1,000 | SY | <b>At discretion of Owner, perform flexible pavement structure repair</b> , provide all labor, materials, equipment, tools, to perform flexible pavement structure repair per TXDOT Item 351, including saw cutting, excavation, installation of 10" of compacted limestone base, and 2" of compacted Type D ACP, all in accordance with the plans, specifications, and scope of work. Owner to identify areas to perform work. <b>Location: Varies</b> |    |      |
|     |       |    |   | \$ | \$ * |
|     |       |    | DOLLARS   |    |      |
|     |       |    | CENTS   |    |      |
|     |       |    |   |    |      |
| 15. | 2,800 | SY | <b>Pulverize Existing Pavement (10" deep)</b> including all labor, material, equipment, to rework the existing paved area, mixing, reshaping, grading, and compaction, for<br><b>Location: SNR Cabin Paving</b>   |    |      |
|     |       |    | DOLLARS   |    |      |
|     |       |    | CENTS   | \$ | \$ * |
|     |       |    | Per Square Yard   |    |      |

\*Do not extend unit prices or total out bid items. Show unit price in words and figures only. In case of discrepancy, the amount shown in words will govern.